

TO:  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING  
 266 N. Main St., Ste. 220  
 Wichita, KS 67202-1513

API Well Number: 15-007-23817-01-00  
 Spot: NENWNWNE Sec/Twnshp/Rge: 10-35S-10W  
5055 feet from S Section Line, 2205 feet from E Section Line  
 Lease Name: JENNIE Well #: 1-10H  
 County: BARBER Total Vertical Depth: 4799 feet

Operator License No.: 34192  
 Op Name: SANDRIDGE EXPLORATION AND PRO  
 Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4733		WITH 50 SX CMT
COND	20	90		WITH 10 SX CMT
	L1 4.5	9142	0	450 sx cement
PROD	7	5241	1700	WITH 185 SX CMT
SURF	10.75	1024		WITH 830 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/22/2016 1:00 PM  
 Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
 Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 4733' WITH 50 SX CMT. PLUG AT 1075' WITH 80 SX CMT. PLUG AT 500' WITH 60 SX CMT. PLUG AT 60' WITH 30 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)  
 Date/Time Plugging Completed: 03/22/2016 4:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4733'. LOAD HOLE WITH MUD & SPOT 50 SX CMT ON TOP OF CIBP THROUGH TBG. 1ST PLUG 1055' WITH 80 SX CMT. 2ND PLUG AT 495' WITH 60 SX CMT. 3RD PLUG AT 62' WITH 30 SX CMT.

*4343'*  
*at inv*

Perfs:

Top	Bot	Thru	Comments
8968	8970		
8886	8888		
8804	8806		
8722	8724		
7960	8290		
7490	8720		
7079	7410		
6668	6999		
6340	6588		
5847	6178		
5437	9052		
5026	5356		

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR SENT\*\* USED CLASS C CEMENT BY ORR ENTERPRISES. TMD = 9142'

Received  
 KANSAS CORPORATION COMMISSION

Plugged through: TBG

APR 11 2016

District: 01  
 RECEIVED  
 MAR 28 2016  
 KCC DODGE CITY

CONSERVATION DIVISION  
 WICHITA, KS  
 Signed Stephen J Pfeifer  
 (TECHNICIAN) *5/16*