

TO: STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING  
 266 N. Main St., Ste. 220  
 Wichita, KS 67202-1513

API Well Number: 15-077-21966-01-00  
 Spot: S2S2S2SE Sec/Twnshp/Rge: 15-35S-8W  
200 feet from S Section Line, 1320 feet from E Section Line  
 Lease Name: BRYANT 3508 Well #: 5-10H  
 County: HARPER Total Vertical Depth: 4798 feet

Operator License No.: 34192  
 Op Name: SANDRIDGE EXPLORATION AND PRO  
 Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	5789		340 SX
SURF	9.625	778		375 SX
T1	4.5	7540		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/29/2016 12:00 AM  
 Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
 Proposal Rcvd. from: RON ORR Company: ORR ENTERPRISES, INC. Phone: \_\_\_\_\_

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL  
 Date/Time Plugging Completed: 04/12/2016 4:30 PM KCC Agent: STEVE VANGIESON

**Actual Plugging Report:**

TUBING STUCK IN HOLE. PERFD AT 5050', PUMPED 30 BBLS OF WATER, TUBING CAME FREE. LAYED DOWN 90 JNTS OF TUBING AND 2000' OF ESP CABLE, STUCK IN HOLE. F P AT 1110' FISHED AND MILLED TO 1138'. COULD PUMP THRU FISH, PUMPED 100 SX CEMENT. LET SET OVERNITE AND PRESSURED TESTED, WOULDN'T HOLD. PUMPED ADDITIONAL 100 SKS AND WELL LOCKED UP. REVERSE CIRCULATE FROM 750' AND LET SET 4 HRS. PRESSURE TESTED TO 300# OK. CUT CASING AT 990' AND RECOVERED. RAN 2 IN TUBING TO 900' AND PUMPED 50 SKS OF CEMENT. PULLED TUBING TO 825' AND SPOTTED 50 SKS OF CEMENT. PULLED TUBING TO 250' AND CIRCUALTED CEMENT TO SURFACE WITH 85 SKS OF CEMENT.

**Perfs:**

Top	Bot	Thru	Comments
7282	7285		
7219	7222		
7147	7150		
7047	7050		
6965	6968		
6899	6902		
6833	6836		
6780	6783		
6657	6660		
6600	6603		
6507	6510		
6453	6456		
6377	6380		
6307	6310		
6237	6240		
6152	6155		
6072	6075		
6012	6015		
5932	5935		
5872	5875		
5797	5800		
5673	5675		
5574	5576		
5475	7490		

*2742  
imw*

Received  
 KANSAS CORPORATION  
**APR 26 2016**  
 CONSERVATION DIVISION  
 WICHITA, KS

Remarks: ORR ENTERPRISES. CLASS C CEMENT. MD = 7540

Plugged through: TBG

District: 02

Signed \_\_\_\_\_

*[Handwritten Signature]*

(TECHNICIAN)

*no 5-6-16*