

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-057-20813-01-00  
Spot: NWNEENE Sec/Twnshp/Rge: 11-28S-21W  
175 feet from N Section Line, 454 feet from E Section Line  
Lease Name: BONES 2821 Well #: 1-11H  
County: FORD Total Vertical Depth: 4955 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5009		WITH 50 SX CMT
COND	20	108		WITH 10 SX CMT
	11 4.5	9645	0	WITH 300 SX CMT
PROD	7	4998	1500	WITH 300 SX CMT
SURF	9.625	1007		WITH 425 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/29/2016 2:00 PM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 5009' WITH 50 SX CMT. PLUG AT 1050' WITH 100 SX CMT. PLUG AT 450' WITH 50 SX CMT. PLUG AT 128' WITH 35 SX CMT TO SURFACE.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: PARTIAL  
Date/Time Plugging Completed: 03/29/2016 5:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

SET CIBP @ 5009' WITH 50 SX CMT. SHUT DOWN. 1ST PLUG AT 1050' WITH 100 SX CMT. 2ND PLUG AT 450' WITH 50 SX CMT. 3RD PLUG AT 128' WITH 35 SX CMT.

Perfs:

Top	Bot	Thru	Comments
8522	8882		
8016	8440		
7440	7876		
6988	7364		
6378	6896		
5822	6234		
5284	9472		

*4690'  
inv*

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR SENT\*\* USED CLASS C CEMENT BY ORR ENTERPRISES. TMD = 9645'.

Received  
KANSAS CORPORATION COMMISSION

Plugged through: TBG

APR 11 2016

District: 01

RECEIVED  
APR - 4 2016  
KCC DODGE CITY

CONSERVATION DIVISION  
WICHITA, KS  
Signed

*Larry A. Davis ECRS*  
(TECHNICIAN)  
*SA*

*205-6-16*