

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-033-20993-00-00  
Spot: SWSWSW Sec/Twnshp/Rge: 10-32S-19W  
330 feet from S Section Line, 330 feet from W Section Line  
Lease Name: BIRD Well #: 3-10  
County: COMANCHE Total Vertical Depth: 5230 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5050		WITH 50 SX CMT
COND	20	95		WITH 250 SX CMT
PROD	4.5	5228	1206	WITH 165 SX CMT
SURF	8.625	665		WITH 450 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/05/2016 1:00 PM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Revd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 4974'. CIRCULATE HOLE WITH MUD & SPOT 10 SX CMT ON TOP OF THE CIBP. PLUG AT 1000' WITH 60 SX CMT. PLUG AT 700' WITH 100 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: PARTIAL  
Date/Time Plugging Completed: 04/05/2016 5:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

4/4/16: SET CIBP @ 5050'. CIRCULATED HOLE WITH 75 BBL MUD & SPOTTED 50 SX CMT ON TOP OF THE CIBP. 4/5/16: TAGGED CMT AT 4522'. 1ST PLUG AT 1000' WITH 60 SX CMT. 2ND PLUG AT 710' WITH 100 SX CMT. 3RD PLUG AT 129' WITH 40 SX CMT. CMT CIRCULATED & THE HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
4975	5188		

KCC WICHITA  
APR 18 2016  
RECEIVED

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR SENT\*\* USED 60/40 POZMIX 4% GEL BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed [Signature]  
SA (TECHNICIAN)

RECEIVED  
APR - 7 2016  
KCC DODGE CITY

[Signature]  
5-6-16