

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-033-20312-00-01
Spot: SESENWNE Sec/Twnshp/Rge: 11-33S-18W
1306 feet from N Section Line, 1323 feet from E Section Line
Lease Name: DONALD M. TODD Well #: 1
County: COMANCHE Total Vertical Depth: 5360 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4952		WITH 10 SX CMT
CIBP		5100		
COND	16	63		WITH 10 SX CMT
PROD	4.5	5350	1542	WITH 225 SX CMT
SURF	8.625	550		WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/13/2016 2:00 PM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 4952' WITH 2 SX CMT. PLUG AT 1190' WITH 10 SX GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: PARTIAL
Date/Time Plugging Completed: 04/13/2016 6:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4952' WITH 10 SX CMT ON TOP OF THE CIBP. 1ST PLUG AT 1000' WITH 60 SX CMT. 2ND PLUG AT 600' WITH 80 SX CMT. 3RD PLUG AT 200' WITH 55 SX CMT. CMT CIRCULATED & THE HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
5108	5164		
5035	5039		
5002	5022		

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED
APR 15 2016
KCC DODGE CITY

Signed [Signature]
REC WICHITA
APR 25 2016
(TECHNICIAN)
RECEIVED

20
5-6-16