

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-033-20398-00-00  
Spot: W2NWNWNW Sec/Twnshp/Rge: 9-33S-19W  
4995 feet from S Section Line, 4955 feet from E Section Line  
Lease Name: FITZWATER Well #: 3A-9  
County: COMANCHE Total Vertical Depth: 5300 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	5300	1038	WITH 250 SX CMT
SURF	8.625	721		WITH 875 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/26/2016 10:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 5066' WITH 10 SX CMT. PLUG AT 1020' WITH 25 SX CMT. PLUG AT 750' WITH 75 SX CMT. PLUG AT 330' WITH 90 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: PARTIAL  
Date/Time Plugging Completed: 04/26/2016 4:45 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

COULD NOT GET ALL RODS & TBG OUT OF THE HOLE. TOP OF THE FISH @ 3420'. COULD NOT GET THE CEMENT RETAINER PAST 1200'. TBG WOULD GO DEEPER BUT 3 ATTEMPTS TO GET THE RETAINER PAST 1200' FAILED. SET THE CMT RETAINER AT 1200 & PUMPED 80 SX CMT TO APPROXIMATELY 4300' WITH AT 50 BBL MUD SPACER TO THE CMT RETAINER. PULLED OUT OF THE RETAINER & PUMPED AN ADDITIONAL 10 SX CMT. LAID DOWN TBG. 1ST PLUG AT 1020 WITH 25 SX CMT. 2ND PLUG AT 750' WITH 75 SX CMT. 3RD PLUG AT 330' WITH 90 SX CMT. CMT CIRCULATED AND THE HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
5116	5190		

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR SENT\*\* USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed [Signature]  
(TECHNICIAN)

RECEIVED  
APR 27 2016  
KCC DODGE CITY [Signature]

KCC WICHITA 51A  
MAY 02 2016  
RECEIVED

Form CP-2/3  
205-6-16