

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-033-20438-00-00
Spot: NWSENW Sec/Twnshp/Rgc: 9-33S-19W
3683 feet from S Section Line, 3629 feet from E Section Line
Lease Name: FITZWATER Well #: 4-9
County: COMANCHE Total Vertical Depth: 5355 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	5355	1632	WITH 200 SX CMT
SURF	8.625	511		WITH 650 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 04/19/2016 12:00 PM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: PARTIAL
Date/Time Plugging Completed: 04/20/2016 2:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

4/19/16: TBG PARTED AT 4368'. SET A CEMENT RETAINER AT 4304'. PUMPED 50 SX CMT BELOW THE RETAINER THEN PULLED OFF OF THE RETAINER & PUMPED AN ADDITIONAL 10 SX CMT. PULLED TBG. 4/20/16: 1ST PLUG AT 1020' WITH 50 SX CMT. 2ND PLUG AT 540' WITH 80 SX CMT. 3RD PLUG AT 64' WITH 20 SX CMT. CMT CIRCULATED & THE HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
5170	5276		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed [Signature]
(TECHNICIAN)

KCC WICHITA [Signature]

MAY 02 2016

RECEIVED

RECEIVED
APR 25 2016
KCC DODGE CITY

Form CP-2/3

NO 5-6-16