

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-033-20350-00-00  
Spot: SWNE Sec/Twnshp/Rge: 8-33S-19W  
3337 feet from S Section Line, 1960 feet from E Section Line  
Lease Name: ZIELKE Well #: 2-8  
County: COMANCHE Total Vertical Depth: 5405 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5087		WITH 10 SX CMT
PROD	4.5	5405	1184	WITH 250 SX CMT
SURF	8.625	849		WITH 350 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/21/2016 9:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 5087' WITH 10 SX CMT. PLUG AT 1000' WITH 50 SX CMT. PLUG AT 500' WITH 60 SX CMT. PLUG AT 64' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/21/2016 10:00 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5087' WITH 10 SX CMT ON TOP OF THE CIBP. 1ST PLUG AT 1000' WITH 100 SX CMT. 2ND PLUG AT 500' WITH 60 SX CMT. 3RD PLUG AT 64' WITH 90 SX CMT. CMT CIRCULATED BUT FELL APPROXIMATELT 30'. TOPPED OFF WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5172			MISSISSIPI
5137	5301		

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR SENT\*\* USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed [Signature]  
(TECHNICIAN)

RECEIVED  
APR 26 2016  
KCC DODGE CITY

KCC WICHITA  
MAY 02 2016  
RECEIVED

Form CP-2/3  
205-6-16