

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-033-20441-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 8-33S-19W
4950 feet from S Section Line, 2310 feet from E Section Line
Lease Name: ZIELKE Well #: 4-8
County: COMANCHE Total Vertical Depth: 5315 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5065		WITH 10 SX CMT
PROD	4.5	5306	1235	WITH 200 SX CMT
SURF	8.625	705		WITH 500 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 04/25/2016 9:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 5065' WITH 10 SX CMT. PLUG AT 1000' WITH 60 SX CMT. PLUG AT 750' WITH 50 SX CMT. PLUG AT 330' WITH 90 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/25/2016 11:20 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5065' WITH 10 SX CMT ON TOP OF THE CIBP. 1ST PLUG AT 1000' WITH 60 SX CMT. 2ND PLUG AT 750' WITH 50 SX CMT. 3RD PLUG AT 330' WITH 85 SX CMT. CMT CIRCULATED. PULLED TBG & TOPPED OFF WITH 5 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5115	5212		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
APR 27 2016
KCC DODGE CITY

JA
KCC WICHITA

MAY 02 2016

RECEIVED

Form CP-2/3

20-5-6-16