

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-129-20807-00-00
Spot: NENW Sec/Twnshp/Rge: 10-33S-41W
5023 feet from S Section Line, 3327 feet from E Section Line
Lease Name: BERRYMAN RICHFIELD UNIT Well #: 19-2
County: MORTON Total Vertical Depth: 5230 feet

Operator License No.: 34832
Op Name: SCOUT ENERGY MANAGEMENT LLC
Address: 4901 LBJ FREEWAY SUITE 300
DALLAS, TX 75244

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	5209	1764	WITH 150 SX CMT
SURF	8.625	1469		WITH 750 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/28/2016 9:30 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: JOHN GARCIA Company: SCOUT ENERGY Phone: (918) 613-9375

Proposed Plugging Method: TBG AT +/- 2434'. CIRCULATE HOLE WITH MUD. SPOT 75 SX CMT & 100# HULLS. WOC. TAG CMT AT 2360' OR HIGHER. PLUG AT 1519' WITH 80 SX CMT. PLUG AT 550' WITH 60 SX CMT. PLUG AT 64' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: PARTIAL
Date/Time Plugging Completed: 03/29/2016 11:00 AM KCC Agent: WADE KLAUS

Actual Plugging Report:

3/24/16: TIH WITH TBG. TOP OF FISH @ 2425'. 3/28/16: CIRCULATED HOLE WITH MUD. PUMPED 75 SX WITH CC. WOC. TAGGED TOC @ 2299'. CUT CASING AT 1764'. 3/29/16: 1ST PLUG AT 1519' WITH 80 SX CMT. 2ND PLUG AT 550' WITH 60 SX CMT. 3RD PLUG AT 64' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5080	5084		

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
APR - 4 2016
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION
APR 11 2016
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3
NO 5-6-16