

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-095-20474-00-00  
Spot: SENESE Sec/Twnshp/Rge: 23-30S-10W  
1650 feet from S Section Line, 330 feet from E Section Line  
Lease Name: PAGENKOPF Well #: 1  
County: KINGMAN Total Vertical Depth: 4684 feet

Operator License No.: 3959  
Op Name: SIROKY OIL MANAGEMENT  
Address: PO BOX 464  
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4420	1736	75 SX
SURF	8.625	253		200 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/30/2016 12:00 AM  
Plug Co. License No.: 34227 Plug Co. Name: AMERICAN WELL SERVICE LLC  
Proposal Rcvd. from: SPENCER SIROKY Company: \_\_\_\_\_ Phone: (620) 770-0969

Proposed Plugging Method: per KCC instructions

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: PARTIAL  
Date/Time Plugging Completed: 04/04/2016 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

CIRCULATED TUBING TO 4341'. MIXED 25 SXS AND SPOTTED. PULLED 12 JTS AND CIRCUALTED HOLE CLEAN. PULLED TUBING, TAGGED W/JARS @ 4000'. EXCEL RAN IN W/ WIRELINE AND CUT CASING @ 1736'. PULLED 2 JTS AND PUMPED 35 SXS @ 1650'. PULLED CASING TO 1150', CIRCUALTE CASING THEN PUMPED 35 SXS AND DISPLACED. PULLED CASING TO 300' AND CIRCUALTED CSG, THEN MIXED 75 SXS TO SURFACE. PULLED CASING TO SURFACE AND TOPPED OFF WELL 4-16-16 CHECKED TOP PLUG, CASING FILLED WITH SOIL, HAD TO WASH 100' OF SOIL OUT OF SURFACE CASING, REPLACED WITH 45 SXS OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
4358	4368		

Remarks: BASIC ENERGY PROVIDED CEMENT FOR THIS JOB. WELL DOWN LONGER THAN 10 YEARS.

Plugged through: CSG

District: 02

Signed [Signature]  
(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

MAY 05 2016

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3

no  
5-6-16

1/4