

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-151-10656-00-01
Spot: SWNENE Sec/Twnshp/Rgc: 31-26S-12W
4318 feet from S Section Line, 1003 feet from E Section Line
Lease Name: BINGER Well #: 2
County: PRATT Total Vertical Depth: 4314 feet

Operator License No.: 9232
Op Name: TIMBERLINE OIL & GAS CORPORATIO
Address: 4000 PENROSE PLACE
RAPID CITY, SD 57702

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 4268 | | |
| PROD | 7 | 4291 | 712 | WITH 300 SX CMT |
| SURF | 10.75 | 642 | | WITH 500 SX CMT |

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 04/01/2016 3:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: BRANT GROTE Company: TIMBERLINE OIL & GAS Phone: (620) 672-8240

Proposed Plugging Method: JUNK LEFT IN HOLE. UNABLE TO FISH ANYMORE OUT. UNABLE TO GET TO BOTTOM TO PLUG. PLUG ON TOP OF CASING STUB WITH 15 SX GEL & 75 SX CMT. PLUG AT 690' WITH 75 SX CMT. PLUG AT 60' WITH CMT TO SURFACE.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/01/2016 4:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

JUNK IN HOLE: 2 3/8" TBG AT 934' TO BOTTOM OF HOLE. TOP OF SUCKER RODS INSIDE TBG AT 860' FROM SURFACE. UNABLE TO GET TO BOTTOM TO PLUG. 1ST PLUG AT 713' WITH 15 SX GEL & 75 SX CMT. 2ND PLUG AT 323' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 30 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4201 | 4242 | | |

Remarks: **COMPLIANCE ISSUE: DENEID TA HIGH FL** USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: TBG

District: 01

Signed *Stephen J. Pfeifer*
(TECHNICIAN)

210
5-6-16

RECEIVED
APR - 4 2016
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION

APR 11 2016

CONSERVATION DIVISION
WICHITA, KS