

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-22849-00-00
Spot: SENENW Sec/Twnshp/Rge: 1-17S-11W
4340 feet from S Section Line, 3068 feet from E Section Line
Lease Name: FREES Well #: 4
County: BARTON Total Vertical Depth: 3600 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3457		150 SX
SURF	8.625	313		180 SX

Well Type: SWD UIC Docket No: D21227.0 Date/Time to Plug: 04/14/2016 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: TRACY BLACK Company: VESS OIL CORPORATION Phone: (620) 791-7048

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/400 # hulls and 16 sx gel. Operator has circulated cement to surface on backside from 700'.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/12/2016 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1350'. Ran tubing to 3400' and pumped 16 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1420' and pumped 65 sx cement w/100 # hulls. Pulled tubing to 700'. Circulated cement to surface w/80 sx cement on casing. Pulled tubing and topped off w/10 sx cement.

GPS: 38.60850 -098.49397

Perfs:

Top	Bot	Thru	Comments
3457	3600		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

District: 04

Signed

Bruce Rodie

KCC WICHITA

(TECHNICIAN)

CM

APR 15 2016

MAY 02 2016

RECEIVED

Form CP-2/3

no
5-6-16
cc WC