

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-22837-00-00
Spot: NENENWNW Sec/Twnshp/Rge: 1-17S-11W
280 feet from N Section Line, 1140 feet from W Section Line
Lease Name: FREES Well #: 3
County: BARTON Total Vertical Depth: 3600 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3455		175 SX
SURF	8.625	277		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/12/2016 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: TRACY BLACK Company: VESS OIL CORPORATION Phone: (620) 791-7048

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/400 # hulls.
Company was going to pull casing and could not get pipe cut to pull casing. Bottom was sanded off and topped with cement.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/12/2016 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped with cement. Perforated at 1300', 700' and 300'. Ran tubing to 1500' and pumped 80 sx cement w/200 # hulls. Pulled tubing to 700'. Circulated cement to surface w/110 sx cement on casing and surface pipe. Pulled tubing and topped off with 50 sx cement.

GPS: 38.60850 -098.49397

Perfs:

Top	Bot	Thru	Comments
3405	3406		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN) *cm*

APR 15 2016

KCC WICHITA

MAY 02 2016

RECEIVED

Form CP-2/3

NO 5-6-16