

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-22653-00-00
Spot: NENWENW Sec/Twnshp/Rge: 1-17S-11W
280 feet from N Section Line, 1700 feet from W Section Line
Lease Name: FREES Well #: 2
County: BARTON Total Vertical Depth: 3381 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3377	1500	125 SX
SURF	8.625	330		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/13/2016 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: TRACY BLACK Company: VESS OIL CORPORATION Phone: (620) 791-7048

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/13/2016 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped with cement. Cut casing at 1500'. Pulled casing to 1350' and pumped 90 sx cement w/100 # hulls. Hole high in the casing had cement to surface. Pulled casing to 1280' and found hole. Tied to casing and pumped 60 sx cement w/100 # hulls. Pulled casing to 950' and pumped 50 sx cement w/100 # hulls. Pulled casing to 700' and pumped 50 sx cement. Pulled casing to 350'. Circulated cement to surface w/50 sx cement. Pulled casing and hole stayed full.

GPS: 38.60850 -098.49165

Perfs:

Top	Bot	Thru	Comments
3377	3381		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

cm

APR 15 2016

KCC WICHITA

MAY 02 2016

RECEIVED

Form CP-2/3

no 5-6-16