

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-21423-00-00
Spot: NESENWSE Sec/Twnshp/Rge: 20-17S-24W
1732 feet from S Section Line, 1612 feet from E Section Line
Lease Name: GERSTNER C Well #: 1
County: NESS Total Vertical Depth: 4343 feet

Operator License No.: 31788
Op Name: VEENKER RESOURCES, INC.
Address: PO BOX 14339
OKLAHOMA CITY, OK 73113

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1700		WITH 2 SX CMT
CIBP		4100		WITH 2 SX CMT
PROD	4.5	4332	0	WITH 100 SX CMT
SURF	8.625	291		WITH 190 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/25/2016 8:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: HAL HOSS Company: CHEYENNE OIL SERVICES Phone: (785) 798-5051

Proposed Plugging Method: CIBP @ 4100' WITH 2 SX CMT. LOAD HOLE & RUN BOND LOG. SET CIBP & PERFORATE IF NEEDED. RUN TBG & SPOT CMT & CIRCULATE. PUMP DOWN BACKSIDE IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/25/2016 2:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SQUEEZED AT 2953-3165' WITH 150 SX CMT. SQUEEZED AT 2564-3250' WITH 150 SX CMT. SQUEEZED AT 2930-3240' WITH 200 SX CMT. SQUEEZED AT 2400-2493' WITH 125 SX CMT. SQUEEZED AT 2142-2174' WITH 350 SX CMT. SQUEEZED AT 1025-1110' WITH 250 SX CMT. SQUEEZED AT 1027-1335' WITH 100 SX CMT SET CIBP @ 4100' WITH 2 SX CMT. RUN BOND LOG 2000' TO SURFACE. FOUND TOP OF CMT AT 2000' THEN CMT AT 1590'-560'. SET CIBP @ 1700' WITH 2 SX CMT. PERFORATED AT 500'. RUN TBG TO 1200' & PUMPED 75 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TIED ONTO CASING & PUMPED 15 SX CMT. PRESSURED TO 500# & HELD. TIED ONTO BACKSIDE & PUMPED 15 SX CMT. PRESSURED TO 400# & HELD.

Perfs:

Top	Bot	Thru	Comments
4332	4343		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

RECEIVED
APR 26 2016
KCC DODGE CITY

Signed Michael A. Maier
(TECHNICIAN)

KCC WICHITA

MAY 02 2016

RECEIVED

720
5-6-16