

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-20262-00-02
Spot: SENENE Sec/Twnshp/Rge: 3-10S-17W
4290 feet from S Section Line, 330 feet from E Section Line
Lease Name: NETTIE UNIT Well #: 9-4
County: ROOKS Total Vertical Depth: 3434 feet

Operator License No.: 30537
Op Name: VENTURE RESOURCES, INC.
Address: 2255 S WADSWORTH BLVD, STE 205
LAKEWOOD, CO 80227

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3473		150 SX
SURF	8.625	331		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/22/2016 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOHN CEARLEY Company: VENTURE RESOURCES, INC. Phone: (785) 688-4174

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/1000 # hulls.
Bridge Plug at 3180' drilled out to 3265'.
LKC Perfs at 3211' - 3445'.
DV Tool at 1307' w/300 sx cement.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/22/2016 1:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perfs:

Ran tubing to 3230' and pumped 75 sx cement w/600 # hulls. Pulled tubing to 2700' and pumped 100 sx cement w/400 # hulls. Pulled tubing to 1600' and pumped 140 sx cement to circulate cement to surface. Pulled all tubing. Topped off 5 1/2" casing w/20 sx cement. Visually checked 8 5/8" x 5 1/2" annulus and cement was to surface.

GPS: 39.21706N -099.19706W

Remarks: SWIFT SERVICES INC. TICKET # 28837

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

KCC WICHITA

MAY 02 2016

RECEIVED

APR 26 2016

Form CP-2/3

205-6-16