

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-23332-00-00
Spot: S2NWNW Sec/Twnshp/Rge: 33-7S-21W
990 feet from N Section Line, 660 feet from W Section Line
Lease Name: BERLAND Well #: 1
County: GRAHAM Total Vertical Depth: 3719 feet

Operator License No.: 34559
Op Name: WM KS ENERGY RESOURCES LLC
Address: 1001 FANNIN, STE 4000
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3719		145 SX
SURF	8.625	210		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/13/2016 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: TOM BERENS Company: WM KS ENERGY RESOURCES LLC Phone: (785) 688-4040

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/800 # hulls.
Port Collar at 1800' w/310 sx cement.
Perforations: 3306' - 3308', 3356' - 3358', 3375' - 3378', 3484' - 3488', 3502' - 3505', 3354' - 3356', 3622' - 3627'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/13/2016 12:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3600' and pumped 75 sx cement w/600 # hulls. Let set one hour. Pulled tubing to 2880' and pumped 100 sx cement. Pulled tubing to 1900' and pumped 100 sx cement. Pulled tubing to 910' and pumped 50 sx cement. Pulled tubing out and topped off casing with 15 sx cement. Tied on to backside and squeezed with 5 sx cement. Shut in pressure 300 psi.

GPS: 39.40591 -099.67475

Perfs:


Top	Bot	Thru	Comments
3554	3556		

Remarks: QUALITY CEMENT TICKET # 7806

Plugged through: TBG

District: 04

Signed _____



(TECHNICIAN)

CM

KCC WICHITA

MAY 02 2016

RECEIVED

APR 15 2016

Form CP-2/3

MO 5-6-16