

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-103-20974-00-00  
Spot: NESWNESE Sec/Twnshp/Rge: 10-10S-21E  
1875 feet from S Section Line, 667 feet from E Section Line  
Lease Name: DOEGE Well #: 1  
County: LEAVENWORTH Total Vertical Depth: 1200 feet

Operator License No.: 30068  
Op Name: RENEGADE RESOURCES CORP.  
Address: 5335 CEDARWOOD DR  
RENO, NV 89511

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	966		75 SX
PROD	4.5	1200		
SURF	7	41		2 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/05/2016 12:00 PM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: CARL M. WELCH Company: RENEGADE RESOURCES CORP. Phone: (775) 849-1150

Proposed Plugging Method: Establish an injection rate into the perfs through swage and valve. Mix and pump measured volume of cement slurry with cottonseed hulls. (app 60 sacks of poz blend I-A plus 6% gel; 20# of cottonseed hulls mixed with slurry) Fill casing to the perfs, plus 5-10 sacks extra out into the perforations. Flush valve with minimal water and shut in. Leaving casing full.

Plugging Proposal Received By: TAYLOR HERMAN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/05/2016 12:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Perfs:

HOOKED UP TO THE PRODUCTION CASING AND SQUEEZED THE WELL FULL OF CEMENT.

Top	Bot	Thru	Comments
850	852	CSG	

RECEIVED  
KCC DIST # 3  
APR 21 2016  
CHANUTE, KS

TH

Remarks:

Plugged through: CSG

District: 03

Signed Taylor C. Herman  
(TECHNICIAN)

KCC WICHITA

APR 25 2016

RECEIVED

Form CP-2/3

no  
5-6-16