

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-079-20584-00-00
Spot: SWNWNENW Sec/Twnshp/Rge: 11-23S-3W
440 feet from N Section Line, 3830 feet from E Section Line
Lease Name: HORN A Well #: 1
County: HARVEY Total Vertical Depth: 3239 feet

Operator License No.: 30878
Op Name: RESSLER WELL SERVICE, INC.
Address: PO BOX 525
BURRTON, KS 67020

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3228		75 SX
SURF	8.875	265		100 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/25/2016 12:00 AM
Plug Co. License No.: 8253 Plug Co. Name: G & L WELL SERVICE, INC.
Proposal Rcvd. from: LARRY RESSLER Company: G & L WELL SERVICE, INC. Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 04/25/2016 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

PUMPED 35 SX CEMENT WITH 3% CC. DOWN TUBING AT 3200', DISPLACED TO 3150'. SHOT TUBING OFF AT 593', SHOT CASING OFF @ 567', PULLED TUBING AND CASING OUT OF HOLE. RAN TUBING INTO 537' SPOTTED 35 SX CEMENT WITH 3% CC. TAGGED @ 450'. RAN TUBING INTO 300' CIRCUALTED TO SURFACE WITH 155 SX OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
3228	3239		

Remarks: COPELAND CEMENTING OUT OF BURRTON FIRST 70 SX WERE CLASS A CEMENT, NEXT 155 SX WERE 60/40 4% POS MIX, TICKET #44097.

Plugged through: TBG

District: 02

Signed

B. J. Hope

(TECHNICIAN)

no 5-6-16

Received
KANSAS CORPORATION COMMISSION

MAY 05 2016

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

1/4