

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-047-00080-00-00
Spot: NENENWNW Sec/Twnshp/Rge: 9-25S-16W
297 feet from N Section Line, 1212 feet from W Section Line
Lease Name: MASSEY Well #: 1
County: EDWARDS Total Vertical Depth: 4297 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S MAIN ST
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3730		WITH 2 SX CMT
PROD	5.5	4297	0	WITH 150 SX CMT
SURF	8.625	280		WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/23/2016 8:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: RANDY GINEST Company: RAMA OPERATING Phone: (620) 234-5191

Proposed Plugging Method: SET CIBP @ 3730' WITH 2 SX CMT. PLUG AT 1180' WITH 13 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE
Date/Time Plugging Completed: 03/23/2016 2:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 3730' & 2 SX CMT. PERFORATE CASING AT 1180'. PUMP 13 SX GEL FOLLOWED BY 50 SX CMT. PLUG TAGGED AT 870'. 39 SX CMT CIRCULATED FROM 300' TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3788	3824		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed Michael Maier
(TECHNICIAN)

no 5-6-16

RECEIVED
MAR 30 2016
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION
APR 11 2016
CONSERVATION DIVISION
WICHITA, KS