

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-04892-00-02  
Spot: SENESE Sec/Twnshp/Rge: 15-20S-12W  
1684 feet from S Section Line, 462 feet from E Section Line  
Lease Name: BUCKBEE B Well #: 3  
County: BARTON Total Vertical Depth: 3420 feet

Operator License No.: 3911  
Op Name: RAMA OPERATING CO., INC.  
Address: 101 S MAIN ST  
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	3369		100 SX
SURF	10.75	601		325 SX

Well Type: SWD UIC Docket No: D26998.0 Date/Time to Plug: 04/05/2016 12:00 AM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: ROBIN AUSTIN Company: RAMA OPERATING Phone: (620) 234-5191

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 400 # hulls and 3400 # gel.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/05/2016 7:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1250' and 640'. Ran tubing to 2970' and pumped 3400 # gel followed by 100 sx cement w/200 # hulls. Pulled tubing to 1250' and pumped 150 sx cement w/200 # hulls. Pulled tubing to 650'. Circulated cement to surface w/100 sx cement. Pulled tubing and topped off with 15 sx cement.

GPS: 38.30920 -098.62746

Perfs:

Top	Bot	Thru	Comments
2945	2985		

Remarks: BASIC ENERGY SERVICES

Plugged through: TGG  
ESG

District: 04

Signed Bruce Rodie  
(TECHNICIAN) CM

APR 08 2015

KCC WICHITA Form CP-2/3  
APR 19 2016  
RECEIVED  
No 5-6-16  
CC UIC