

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-155-02286-00-01
Spot: SWSWSW Sec/Twnshp/Rge: 32-23S-10W
374 feet from S Section Line, 4971 feet from E Section Line
Lease Name: BORDIN OWWO Well #: 1-32
County: RENO Total Vertical Depth: 1950 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S MAIN ST
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	1500		
PROD	5.5	1825	1464	100 SX
SURF	8.625	267		150 SX
T1	2.375	1725		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/08/2016 10:30 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: RANDY GINEST Company: RAMA OPERATING CO. Phone: (620) 234-5191

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: B. J. HOPE WitnessType: PARTIAL
Date/Time Plugging Completed: 04/08/2016 2:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SET CIBP @ 1500' AND CAP WITH 2 SX'S CEMENT. SHOOT CASING OFF AT 1464' AND PULL 1 JT. OUT. PUMP 35 SX'S COMMON CEMENT WITH 3% CC AT 1435', PULL CASING ON UP TO 950'. WAIT AWHILE AND TAG CEMENT WITH SWAB BAR AT 1300'. PUMP 35 SX'S COMMON WITH 3% CC AT 950', PULL CASING TO 310' AND CIRCUALTE 60-40 POZ, 4% GEL TO SURFACE. PULL CASING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
1689	1694		CSG
1562	1694		

Remarks: LOG TECH OF KS. #8701. BASIC CEMENT #13435. T.A. N.O.V. LETTER WAS SENT.

Plugged through: CSG

District: 02

Signed Virgil Clothier
KCC WICHITA (TECHNICIAN)

APR 25 2016

RECEIVED

70
5-6-16
Form CP-2/3