

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-025-20263-00-00  
Spot: SWSE Sec/Twnshp/Rge: 20-31S-21W  
660 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: MOORE Well #: 3-20  
County: CLARK Total Vertical Depth: 5350 feet

Operator License No.: 4824  
Op Name: PIONEER NATURAL RESOURCES USA,  
Address: 5205 N. O CONNOR BLVD., SUITE 200  
IRVING, TX 75039

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5130		WITH 10 SX CMT
PROD	4.5	5340	1298	WITH 200 SX CMT
SURF	8.625	627		WITH 300 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/06/2016 8:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Revd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: SET CIBP @ 5130' WITH 10 SX CMT. RUN TBG TO 1140' & 50 SX CMT. PLUG AT 650' WITH 80 SX CMT. PLUG AT 60' WITH CMT TO SURFACE.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: PARTIAL  
Date/Time Plugging Completed: 04/06/2016 5:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5130' WITH 10 SX CMT ON TOP OF CIBP. 1ST PLUG AT 1140' WITH 50 SX CMT. 2ND PLUG AT 650' WITH 80 SX CMT BUT NO CIRCULATION. WAITED 4 HOURS & TAGGED CMT AT 347'. 3RD PLUG AT 64' WITH 20 SX CMT. CMT CIRCULATED & THE HOLE STAYED FULL.

**KCC WICHITA**  
**APR 18 2016**  
**RECEIVED**

Perfs:

Top	Bot	Thru	Comments
5181	5190		

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.  
Plugged through: TBG

District: 01

Signed Eric MacLaren  
SA (TECHNICIAN)

RECEIVED  
APR 13 2016  
KCC DODGE CITY MR

Form CP-2/3  
NO  
5-6-16