

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-205-28357-00-00  
Spot: SWSESE Sec/Twnshp/Rge: 23-29S-14E  
330 feet from S Section Line, 990 feet from E Section Line  
Lease Name: G NEILL TRUST Well #: D4C-23  
County: WILSON Total Vertical Depth: 1135 feet

Operator License No.: 35207  
Op Name: POLARIS ENERGY, INC.  
Address: PO BOX 85  
MAINEVILLE, OH 45039

| String | Size  | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| CIBP   |       | 1056       |             |         |
| PROD   | 4.5   | 1132       |             | 30 SX   |
| SURF   | 8.625 | 41         |             | 40 SX   |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/01/2016 12:00 PM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP  
Proposal Rcvd. from: AARON HAMMERSCHMID Company: DART CHEROKEE Phone: (620) 331-7870

Proposed Plugging Method: TIH to 1056'. Set cmt plug fr 1056' - surf. Cut off csg. Restore loc.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE  
Date/Time Plugging Completed: 03/01/2016 12:00 PM KCC Agent: ALAN DUNNING

**Actual Plugging Report:**

A cement string was lowered to 1050'. The well was then pumped full of cement from btm to top thru the cement string. The cement string was removed and the well topped off with cement. A total of 196 sacks of portland cement were used to plug well. The wellhead was cut off below plow depth and the location restored.

**Perfs:**

| Top   | Bot  | Thru | Comments |
|---|------|------|----------|
| 1060  | 1074 |      |          |
| RECEIVED<br>KCC DIST #3<br>APR 08 2016<br>CHANUTE, KS<br><br>AD |      |      |          |

Remarks:

Plugged through: CSG

District: 03

Signed

Alan Dunning  
(TECHNICIAN)

KCC WICHITA

APR 15 2016

RECEIVED

Form CP-2/3

no  
5-6-16