

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-095-21652-00-01  
Spot: SWNW Sec/Twnshp/Rge: 22-27S-7W  
3300 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: PULLIAM Well #: 1  
County: KINGMAN Total Vertical Depth: 3917 feet

Operator License No.: 34848  
Op Name: POLLOK ENERGY, LLC  
Address: 501 N. 4TH PO BOX 106  
PURCELL, OK 73080

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	300		180 SX

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/13/2016 8:00 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: DAVID HICKMAN Company: POLLOCK Phone: (620) 253-6588

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/13/2016 11:45 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

SET CIBP 3528' AND CAPPED WITH 2 SKS OF CEMENT, RECOVERED CASING FROM 2490' AND PULLED FROM THE WELL BORE. RAN TUBING TO 1105' AND SPOTTED 35 SKS, PULLED TUBING TO 617', AND SPOTTED 35 SKS OF CEMENT. PULLED TUBING TO 357', AND CIRCUALTED CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3578	3584		

Remarks: BASIC ENERGY SERVICES. COMMON AND 60/40

Plugged through: TBG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

APR 26 2016

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3

220  
5-6-16