

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-26178-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 28-14S-17W
2264 feet from S Section Line, 2264 feet from E Section Line
Lease Name: HERL 'A' Well #: 6
County: ELLIS Total Vertical Depth: 3605 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3597	1830	200 SX
SURF	8.625	1121		400 SX
T1	2.875	3496		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/07/2016 11:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMMIE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Perfs: 3204' - 3208', 3254' - 3260', 3276' - 3282', 3310' - 3314', 3394' - 3398', 346' - 3472', 3478' - 3486', 3492' - 3496'.
Method: PBTD: 3576'

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/07/2016 2:40 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Sanded off bottom to 3130'. Topped off with 5 sx cement. Cut casing at 1830'. Pulled casing to 1650' and pumped 165 sx cement w/300 # hulls. Pulled casing to 1137' and pumped 50 sx cement w/100 # hulls. Pulled casing to 590' and pumped 120 sx cement w/100 # hulls to circulate cement to surface. Pulled casing and topped off hole with 0 sx cement. Hole standing full.

GPS: 38.80498 -099.21557

Perfs:

Top	Bot	Thru	Comments
3492	3496		
3478	3486		
3466	3472		
3394	3408		
3310	3314		
3276	3282		
3254	3260		

Remarks: QUALITY OIL WELL CEMENTING TICKET # 1532

Plugged through: CSG

District: 04

Signed _____

(TECHNICIAN)

KCC WICHITA

APR 19 2016

RECEIVED

Form CP-2/3

20-5-6-16

APR 08 2016