

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-19205-00-01
Spot: NENWSE Sec/Twnshp/Rge: 24-15S-12W
2295 feet from S Section Line, 1657 feet from E Section Line
Lease Name: HEINZE Well #: 1
County: RUSSELL Total Vertical Depth: 3300 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 5.5 | 3290 | | 200 SX |
| SURF | 8.625 | 288 | | 115 SX |

Well Type: EOR UIC Docket No: E26822.1 Date/Time to Plug: 04/11/2016 8:00 AM
Plug Co. License No.: 34071 Plug Co. Name: PATRIOT WELL SERVICE, INC.
Proposal Rcvd. from: TODD L. DINKEL Company: GLM COMPANY Phone: (785) 639-5415

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls and 1000 # gel. Surface pipe has cement to surface.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/11/2016 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1350', 740' and 300'. Ran tubing to 2800' and pumped 1000 # gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1300' and pumped 60 sx cement w/100 # hulls. Pulled tubing to 740'. Circulated cement to surface with 125 sx cement. Pulled tubing and topped off with 10 sx cement.

GPS: 38.73233 -098.60226

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3014 | 3175 | | LKC |
| 2902 | 2906 | | TORONTO |

Remarks: GLOBAL SERVICES

Plugged through: TBG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

KCC WICHITA

MAY 02 2016

RECEIVED

APR 15 2016

Form CP-2/3

MO 5-6-16 CC WCC