

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-22730-00-00
Spot: NENENWSE Sec/Twnshp/Rge: 24-15S-13W
2525 feet from S Section Line, 1500 feet from E Section Line
Lease Name: LUERMAN-PIESTER Well #: 1-WS
County: RUSSELL Total Vertical Depth: 822 feet

Operator License No.: 30606 String Size Depth (ft) Pulled (ft) Comments
Op Name: MURFIN DRILLING CO., INC. PROD 5.5 819 225 SX
Address: 250 N WATER STE 300
WICHITA, KS 67202

Well Type: WSW UIC Docket No: Date/Time to Plug: 04/05/2016 8:00 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: MARK ROBBEN Company: MURFIN DRILLING Phone: (785) 483-1197

Proposed Plugging Method: Ordered 100 sx 60/40 pozmix 4% gel cement w/400 # hulls.
Old water supplu well with 5 1/2" casing to 819'. Cemented from top to bottom.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/05/2016 11:00 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 750' and pumped 35 sx cement w/100 # hulls. Pulled tubing to 375'. Circulated cement to surface with 45 sx cement. Pulled tubing and topped off with 15 sx cement.
GPS: 38.73280 -098.71318

Perfs:

Top	Bot	Thru	Comments
758	760		
745	747		
719	721		
700	702		
676	678		
654	656		
624	626		
600	607		
587	589		
579	581		
555	557		
536	538		
526	528		
501	760		
500	504		

Remarks: HURRICANE SERVICES

Plugged through: TBG

District: 04

Signed Bruce Rodie
(TECHNICIAN) CM

APR 08 2016

KCC WICHITA Form CP-2/3
APR 19 2016 RECEIVED
NO 5-6-16