

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-01486-00-01
Spot: SWSWNE **Sec/Twnshp/Rge:** 6-9S-17W
2932 feet from S Section Line, 2347 feet from E Section Line
Lease Name: GARVERT **Well #:** 1
County: ROOKS **Total Vertical Depth:** 3492 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

<u>String</u>	<u>Size</u>	<u>Depth (ft)</u>	<u>Pulled (ft)</u>	<u>Comments</u>
PROD	5.5	3356		100 sx
SURF	8.625	165		125 sx

Well Type: EOR **UIC Docket No:** E19154.1 **Date/Time to Plug:** 04/04/2016 10:00 AM
Plug Co. License No.: 30606 **Plug Co. Name:** MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER **Company:** MURFIN DRILLING CO., INC. **Phone:** (785) 421-2103

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement w/800 # hulls.
Perforations: 3084' - 3394'.
Squeezed at 840' w/225 sx cement.
Squeezed at 2449' - 2980' w/200 sx cement.
Bridge plug stuck at 3030'.

Plugging Proposal Received By: RICHARD WILLIAMS **WitnessType:** COMPLETE (100%)
Date/Time Plugging Completed: 04/04/2016 2:00 PM **KCC Agent:** PAT BEDORE

Actual Plugging Report:

Perforated 2 holes at 1260'. Ran tubing. Tagged bridge plug at 3030'. Pulled tubing up to 3020' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 2011' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1265' and pumped 85 sx cement to circulate cement to surface. Pulled all tubing. Hooked to 5 1/2" casing and pumped 65 sx cement. Shut in pressure 50 psi. Hooked to 8 5/8" x 5 1/2" annulus and pumped 50 sx cement. Shut in pressure 60 psi.

GPS: 39.30036N -099.25935W

Perfs:

<u>Top</u>	<u>Bot</u>	<u>Thru</u>	<u>Comments</u>
3356	3394		
3298	3322		
3104	3274		
3084	3087		
3072	3302		

Remarks: HURRICANE SERVUCES INC. TICKET # 10711

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

cm

KCC WICHITA

MAY 02 2016

RECEIVED

APR 08 2016

Form CP-2/3

*no
5-6-16
cc uic*