

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-19128-00-01
Spot: NWSESW Sec/Twnshp/Rge: 12-34S-5E
370 feet from S Section Line, 4456 feet from E Section Line
Lease Name: LANDM Well #: 2
County: COWLEY Total Vertical Depth: 3001 feet

Operator License No.: 34058
Op Name: MUSGROVE ENERGY INC.
Address: PO BOX 2287
PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2998		55 SX
SURF	10.75	104		85 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/21/2016 8:00 AM
Plug Co. License No.: 31539 Plug Co. Name: SAMS WELL SERVICE, INC.
Proposal Rcvd. from: GARY ANSTINE Company: MUSGROVE ENERGY Phone: (620) 441-8165

Proposed Plugging Method: AS PER KCC RULES & REGS / CIBP @ 2940 W/4 SXS, CIRCULATE 250'-0'.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 03/24/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE, SET CIBP @ 2965'. DUMP BAILED 3 SXS CEMENT ON TOP OF CIBP. RIH ON WIRELINE @ 250', PERFORATED SQUEEZE HOLES @ 250'-251'. 3-23-2016, RIH W/TBG @ 258', CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 28 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED DOWN TUBING, SWEDGED INTO 4 1/2" CASING, CONSOLIDATED OILWELL SERVICES MIXED & PUMPED 212 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. 3-24-2016, RIH W/ 1" TBG ON BACKSIDE @ 48', CONSOLIDATED MIXED & PUMPED 22 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. CONSOLIDATED CEMENT TICKET #'S 51236, 51237.

Perfs:

Top	Bot	Thru	Comments
2998	3001		OH

Remarks: COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02

Signed DUANE KRUEGER
(TECHNICIAN)

700
5-6-16

KCC WICHITA

APR 25 2016

RECEIVED

✓