

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-035-02135-00-00  
Spot: SWSENESE Sec/Twnshp/Rge: 12-34S-5E  
1581 feet from S Section Line, 614 feet from E Section Line  
Lease Name: WALDSCHMIDT Well #: 2  
County: COWLEY Total Vertical Depth: 2947 feet

Operator License No.: 34058  
Op Name: MUSGROVE ENERGY INC.  
Address: PO BOX 2287  
PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	3.5	2935	338	40 SXS
PROD	5.5	2860		75 SX
SURF	10.75	91		75 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/21/2016 8:00 AM  
Plug Co. License No.: 31539 Plug Co. Name: SAMS WELL SERVICE, INC.  
Proposal Rcvd. from: GARY ANSTINE Company: MUSGROVE ENERGY Phone: (620) 441-8165

Proposed Plugging Method: AS PER KCC RULES & REGS/ CEMENT BOTTOM PLUG, PULL LINER, PERF CSG, CIRCUALTE 250'-0'.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL  
Date/Time Plugging Completed: 03/23/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2905', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCUALTION, MIXED & PUMPED 35 SXS CLASS A COMMON 2% CC & DISPLACED IN CASING. LAYED TUBING DOWN, TAGGED CEMENT PLUG @ 1877'. RIH ON WIRELINE, CUT 3.5" LINER @ 1802'. LAYED DOWN 338' OF 3 1/2" CASING (16 JOINTS). RIH ON WIRELINE @ 250', PERFORATED SQUEEZE HOLES @ 250'. 3-23-2016 RIH W/TBG @ 254', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 143 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCUALTED. LAYED DOWN TUBING, TOPPED WELL BACK TO SURFACE W/ 11 SXS. CONSOLIDATED CEMENT TICKET #S 51235, 51238.

Perfs:

Top	Bot	Thru	Comments
2935	2947	OH	

Remarks: COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER  
(TECHNICIAN)

no 5 to 16

KCC WICHITA

APR 25 2016

RECEIVED

SK