

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-00399-00-00
Spot: SWSENE Sec/Twnshp/Rge: 27-30S-8W
2970 feet from S Section Line, 990 feet from E Section Line
Lease Name: BOYLE A (WSU 37) Well #: 1
County: KINGMAN Total Vertical Depth: 4800 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4799	175	175 SX
SURF	8.625	200	150	150 SX

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 03/28/2016 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 04/04/2016 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

CHECKED HOLE, TD WAS AT 4315', RAN TUBING TO 4260', PUMPED 35 SACKS COMMON, 3% CC, 150# HULLS, PULLED TUBING OUT, TAGGED CEMENT AT 3810', CUT CASING OFF AT 1600', PULLED CASING TO 1350', PUMPED 35 SACKS COMMON, 3% CC, 100# HULLS, PULLED CASING TO 850', TAGGED CEMENT AT 966', PUMPED 35 SACKS COMMON, 3% CC, 100# HULLS AT 850', PULLED CASING TO 250', CIRCUALTED WITH 110 SACKS COMMON TO SURFACE, PULLED REST OF CASING, TOPPED OFF WITH 20 SACKS COMMON, SET STEEL PLATE ON SURFACE.

Perfs:

Top	Bot	Thru	Comments
4297	4397		

Remarks: QUALITY WELL SERVICE PROVIDED CEMENT FOR THIS JOB. WELL DOWN FOR MORE THAN 10 YEARS.

Plugged through: CSG

District: 02

Signed B. J. Hope

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

MAY 05 2016
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

no
5-6-16

18