

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-095-00905-00-00  
Spot: SWNENW Sec/Twnshp/Rge: 26-30S-8W  
4290 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: BOYLE P (WSU 27) Well #: 1  
County: KINGMAN Total Vertical Depth: 4440 feet

Operator License No.: 33999  
Op Name: LINN OPERATING, INC.  
Address: 600 TRAVIS STE 5100  
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4449	100	100 SX
SURF	8.625	160	150	150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/30/2016 12:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE Phone: \_\_\_\_\_

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 04/04/2016 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

EXCEL WIRELINE SHOOT TUBING FREE AT 4234', PUMPED 35 SACKS COMMON, 3% CC, 150# HULLS, PULLED TUBING OUT, HAD EXCEL PERFORATE AT 1350', 875', AND 250', RAN BAILOR IN, TAGGED CEMENT AT 3990', RAN TUBING TO 1350', PUMPED 35 SACKS COMMON, 3% CC, 100# HULLS, PULLED TUBING OUT, TAGGED CEMENT AT 975', RAN TUBING TO 875', PUMPED 50 SACKS COMMON 3% CC, 100# HULLS, PULLED TUBING TO 250', PUMPED 75 SACKS COMMON, CIRCUALTED OUT 5 1/2" CASING, PULLED TUBING OUT, HOOKED UP TO 5 1/2" CASING, PUMPED 35 SACKS COMMON, CIRCUALTED OUT 8 5/8" SURFACE, CUT CASING AND SURFACE OFF 4' BELOW GROUND, TOPPED OFF WITH 30 SACKS COMMON, WELDED PLATE ON SURFACE.

Perfs:

Top	Bot	Thru	Comments
4357	4367		

Remarks: QUALITY WELL SERVICE PROVIDED CEMENT FOR THIS JOB. WELL DOWN MORE THEN 10 YEARS.

Plugged through: TBG

District: 02

Signed B. J. Hope  
(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

MAY 05 2016  
CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3  
no 5-6-16