

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-01118-00-00
Spot: SESESW Sec/Twnshp/Rge: 18-30S-7W
330 feet from S Section Line, 2310 feet from W Section Line
Lease Name: EARL JOHNSON Well #: 1
County: KINGMAN Total Vertical Depth: 4390 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 5.5 | 4388 | | 250 SX |
| SURF | 8.625 | 207 | | 225 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/07/2016 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 04/07/2016 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

CHECKED HOLE, KNOCKED BRIDGE OUT AT 840'. TD AT 3855', RAN TUBING TO 3855', PUMPED 35 SACKS COMMON, 3% CC, 150# HULLS, PULLED TUBING OUT, HAD EXCEL WIRELINE PERFORATE AT 1150', 750', AND 255'. RAN TUBING TO 1150', PUMPED 35 SACKS COMMON, 3% CC, 100# HULLS, PULLED TUBING OUT, SWEDGE IN, TAGGED CEMENT AT 844', RAN TUBING TO 750', PUMPED 50 SACKS COMMON, 3% CC, 100# HULLS, PULLED TUBING TO 255', PUMPED 80 SACKS COMMON TO SURFACE IN 5 1/2" CASING, PUMPED 40 SACKS COMMON, CIRCUALTED OUT 8 5/8" SURFACE, TOPPED WELL OFF WITH 20 SACKS CEMENT, PUT PLATE ON SURFACE.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4206 | 4298 | | |

Remarks: QUALITY WELL SERVICE PROVIDED CEMENT FOR THIS JOB. WELL DOWN FOR MORE THAN 10 YEARS.

Plugged through: TBG

District: 02

Signed B. J. Hope
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

MAY 05 2016

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

20-5-6-16

18