

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-00600-00-00
Spot: NWSESE Sec/Twnshp/Rge: 19-30S-7W
990 feet from S Section Line, 990 feet from E Section Line
Lease Name: HOSTETTLER Well #: 1
County: KINGMAN Total Vertical Depth: 4800 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4300	100	
PROD	4.5	4305		100 SX
SURF	8.625	193	150	225 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/04/2016 12:00 AM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE Phone: _____

Proposed
Plugging
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK

WitnessType: PARTIAL

Date/Time Plugging Completed: 04/17/2016 4:00 PM

KCC Agent: B. J. HOPE

Actual Plugging Report:

BRIDGE AT 800', KNOCKED OUT BRIDGE WITH BAILOR, TD WELL AT 4300',
PERFORATED AT 1350', 800', AND 250', RAN TUBING TO 4230', PUMPED 35 SACKS
COMMON, 3% CC, 150# HULLS, PULLED TUBING TO 3540', TAGGED CEMENT AT
3720', PULLED TUBING TO 1350', PUMPED 35 SACKS COMMON, 3% CC, 100# HULLS,
PULLED TUBING OUT, RAN BAILOR IN, TAGGED CEMENT AT 1070', RAN TUBING
TO 800', PUMPED 50 SACKS COMMON, 3% CC, 100# HULLS, PULLED TUBING TO
250', PUMPED 50 SACKS COMMON, CIRCULATED OUT 5 1/2" CASING, PULLED
TUBING OUT, HOOKED UP TO 5 1/2" CASING, PUMPED 55 SACKS COMMON,
CIRCULATED OUT 8 5/8", TOPPED WELL OFF WITH 30 SACKS DRY CEMENT, PUT
PLATE ON SURFACE.

Perfs:


Top	Bot	Thru	Comments
4246	4293		

Remarks: QUALITY WELL SERVICE PROVIDED CEMENT FOR THIS JOB. WELL DOWN FOR MORE THAN 10 YEARS.

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

MAY 05 2016

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

no 5-6-16

