

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-00604-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 30-30S-7W
4950 feet from S Section Line, 2310 feet from E Section Line
Lease Name: HOSTETLER Well #: 2
County: KINGMAN Total Vertical Depth: 4800 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	0	0		0 SX
PROD	5.5	4396	1620	
SURF	0	0		0 SX
SURF	8.625	279		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/06/2016 12:00 AM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: _____

Proposed Plugging Method: PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 04/07/2016 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

Perfs:

CHECKED HOLE, TD AT 4310', HOOKED UP TO 5 1/2" CASING, PUMPED 35 SACKS COMMON, 150# HULLS, DISPLACED WITH 98 BBLs OF WATER TO 3850', SHUT IN AT 400 PSI, TAGGED CEMENT AT 3815', RIPPED CASING AT 1620', PULLED CASING TO 1350', PUMPED 35 SACKS COMMON, 3 % CC, 150# HULLS, WAITED 2 HOURS, TAGGED CEMENT AT 1015', PUMPED 35 SACKS 3% CC, 100# HULLS AT 800', PULLED CASING TO 320', PUMPED 160 SACKS COMMON TO SURFACE, PULLED REST OF CASING, TORE DOWN FLOOR AND RIG. PUT PLATE ON 8 5/8" SURFACE.

Remarks: QUALITY WELL SERVICE PROVIDED CEMENT FOR THIS JOB. WELL DOWN FOR MORE THAN 10 YEARS.

Plugged through: CSG

District: 02

Signed B. J. Hope
Received KANSAS CORPORATION COMMISSION (TECHNICIAN)

770
5-6-16

MAY 05 2016

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

JK