

15095-20619-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kingman County, Sec. 36 Twp. 28S Rge. 6 E/W
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines
Approx. C NW SE


Lease Owner Graves Drilling Co., Inc.
Lease Name Victor Well No. 2
Office Address 910 Union Center, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole) Dry hole

Date Well completed 16 August 1977
Application for plugging filed 16 August 1977
Application for plugging approved 16 August 1977
Plugging commenced 16 August 1977
Plugging completed 16 August 1977
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin
Producing formation Depth to top Bottom Total Depth of Well 3995
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 240 feet. Followed by wooden plug and 1/2 sack hulls. Placed 40 sacks cement onto hulls. Mudded up with heavy mud to 40 feet followed by wooden plug, 1/2 sack hulls and 12 sacks cement to base of well cellar. Plugged rat hole with 5 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
9-2-77
SEP 02 1977

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc.
910 Union Center, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
John C. Graves (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John C. Graves
910 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of September, 1977

Courtney M. Graves
Courtney M. Graves Notary Public.

My commission expires 2 February 1980



15-095-20619-0000

ROTARY DRILLERS' LOG

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMMENCED: 8 Aug. 1977
 910 Union Center
 Wichita, Kansas 67202

OPERATOR: Graves Drilling Co., Inc. DRILLING COMPLETED: 16 Aug. 1977
 910 Union Center
 Wichita, Kansas 67202

CASING RECORD: 5 Jts. 225' 8-5/8" used LOCATION: Victor No. 2
 cemented with 170 sacks Approx. C NW SE
 Section 36-28S-6W
 Kingman County, Kansas

0 - 923 Red bed & shale
 923 - 3603 Shale & lime
 3603 - 3632 Lime & shale
 3632 - 3860 Lime
 3860 - 3917 Shale & lime
 3917 - 3995 Chert
 3995 Rotary Total Depth

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By *John Graves*
President

STATE OF KANSAS)
) SS:
 SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public, this 1st day of September, 1977

My commission expires: 2 February 1980

Courtney M. Graves
Courtney M. Graves Notary Public



RECEIVED
STATE COMMISSION
SEP 02 1977
CONSERVATION DIVISION
Wichita, Kansas