

WELL PLUGGING RECORD

Kingman County. Sec. 22 Twp. 28 Rge. (E) 7 (W)

Location as "NE/CNW%SW%" or footage from lines C SE NW

Lease Owner Shawver Armour, Inc.

Lease Name Richardson Well No. 1

Office Address 817 Central Building, Wichita, Kansas

Character of well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 15th 19 61

Application for plugging filed " 19 61

Application for plugging approved " 19 61

Plugging commenced " 19 61

Plugging completed " 19 61

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

'Name of Conservation Agent who supervised plugging of this well Mr. Eugene H. Graham

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4469 Feet

Show depth and thickness of all water, oil and gas formations.

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 240'

1 Plug Howco plug 20 sacks cement & 1/4 sack Hulls

Heavy Mud to 35'

2 Plug Howco Plug 1/4 sack Halls & 10 sacks Cement
2 sacks in rat hole

STATE OF KANSAS
OCT 26 1961
10-26-61
CONSERVATION DIVISION
Wichita Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shawver Armour, Inc.

Address 817 Central Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
H. D. Shawver (~~XXXXXX~~) or (owner of

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

H. D. Shawver, 817 Central Building
Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of October, 1961

My commission expires Dec. 29th, 1963

Marjorie Hall

Notary Public.

15095-00041-0000

DRILLER'S LOG

FARM NAME: RICHARDSON # 1 LOCATION: C SE NW Sec. 22-28-7W
CONTRACTOR: SHAWVER ARMOUR, INC. Kingman County, Kansas
OWNER: SHAWVER ARMOUR, INC. ELEVATION: 1624 K B
COMMENCED: September 30, 1961 COMPLETED: October 15, 1961
CASING RECORD: 262' 8 5/8" w/249 sacks cement & 2 1/2% cc

FORMATION:

TOPS:

Shale & Shells 840
Shale & Lime 1410
Lime 1545
Lime & Shale 1840
Shale & Lime 1905
Lime & Shale 2745
Lime 2855
Lime & Shale 3190
Shale & Lime 3295
Kansas City Lime 3363
Lime 3781
Lime & Shale 3845
Lime 3902
Lime & Shale 4048
Shale & Lime 4082
Mississippian Chat 4162
Mississippian Lime & Chert 4225
Mississippian Lime & Chat 4256
Lime & Chert 4286
Lime 4321
Lime & Shale 4402
Shale & Lime 4450
Lime 4453
Viola 4468
Simpson 4469
ROTARY TOTAL DEPTH 4469

Lansing 3301
Mississippi 4076
Kinderhook 4329
Viola 4453
Simpson 4468

RECEIVED
STATE CORPORATION COMMISSION
OCT 26 1961
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS }
SEDGWICK COUNTY } ss

I, H. D. Shawver, do hereby certify that the above log is a true and correct copy of the above captioned well as shown on the daily drilling reports.

SHAWVER ARMOUR, INC.

BY H. D. Shawver
H. D. Shawver

Subscribed and sworn to before me this 24th day of October, 1961.

My commission expires Dec. 29th, 1963.

Marjorie Hall
Marjorie Hall, Notary Public