

STATE OF KANSAS
STATE CORPORATION COMMISSION
207 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-095018450001

LEASE NAME Alameda Unit

WELL NUMBER TR3- #2

660 Ft. from S Section Line

1,980 Ft. from ^WE Section Line

SEC. 22 TWP. 28S RGE. 7 (X) or (W)

COUNTY Kingman

Date Well Completed 1-12-62

Plugging Commenced 11-26-90

Plugging Completed 11-29-90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Texaco Inc.

ADDRESS P.O. Box 779, Kingfisher Okla. 73703

PHONE (405) 375-5713 OPERATORS LICENSE NO. 5153

Character of Well Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by STEVE VANGIASON (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, Is well log attached? _____

Injection
Producing Formation Lansing-Kc "M" Depth to Top 3,680' Bottom 3,687' ^{PB.} T.D. 3,925'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Lansing-Kansas City</u>	<u>Water</u>	<u>Surface</u>	<u>271'</u>	<u>8 5/8"</u>	<u>271'</u>	<u>0</u>
		<u>0</u>	<u>4,432</u>	<u>4 1/2"</u>	<u>4,432</u>	<u>0</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set
11-20-90. Set CIBP 3534' cap with 2 sacks cmt. Shot 4 squeeze holes in 4 1/2" @ 1100' and 600' and 300'. Ran in hole w 2 3/8 tbg to 1150'. Pump 35 sacks cmt Plug. Pull tbg to 350'. Pump 35 sacks cmt. Plug. Pump 280 sacks cmt - Circ up 8 5/8" to surface. Shut in 11-29-90. Cut off 3' below surface. Weld on cap.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Texaco Inc.

Address P.O. Box 326, Enid Okla. 73703

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Texaco Inc.

STATE OF OKLAHOMA COUNTY OF KINGFISHER, ss.

Gib Arterburn (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Gib Arterburn

(Address) Box 326 Enid OK 73701

SUBSCRIBED AND SWORN TO before me this 5 day of December, 19 90

M. J. Jones
Notary Public

My Commission Expires: September 21, 1991



RECEIVED
STATE CORPORATION COMMISSION
License No. 5153
DEC 6 1990
12-6-90
CONFERENCE DIVISION
Wichita, Kansas