

TE OF KANSAS
TE CORPORATION COMMISSION
S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-095-19005-0001
LEASE NAME Alameda Unit
WELL NUMBER 3-1 (Gurthier #1)
 Ft. from S Section Line
 Ft. from E Section Line
SEC. 22 TWP. 28 SRGE. 7W (W)

LEASE OPERATOR K.C. RESOURCES INC.
ADDRESS P.O. Box 1118, Cardiff, CA 92007
PHONE (760) 753-3330 OPERATORS LICENSE NO. 03880

Date Well Completed 1962
Plugging Commenced 1-5-99
Plugging Completed 1-9-99

Character of Well Water Disposal

(i.e., Gas, D&A, SWD, Input, Water Supply Well)

A plugging proposal was approved on 1-5-99 (date)
Michael Wilson District # 2 (KCC District Agent's Name).

ACO-1 filled? If not, is well log attached?

Producing Formation Viola/Simpson/Arbuckle Depth to Top 4360' Bottom 4775' T.O. 4775'

Arbuckle

Log depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Viola/Simpson	4360-4402					
Arbuckle	4500-4775	Surface	273'	8 5/8"	273'	None
		Prod.	4500'	5 1/2"	4500'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug material was used, state the character of same and depth placed, from feet to feet each set.
1-7-99 Pumped down tubing a 150 sk. cement plug to bottom of hole. 60/40 poz, 2% gel, 2% cal. 1-8-99 Pumped a 50 sk cement plug to 925'. Tagged top at 718'. Set 5 1/2" CIBP at 720'. Perf. 2 holes at 715'. Pumped a 50 sk cement plug and squeezed behind casing. Pumped another 50 sk plug to 715', shut down. 1-9-99 tagged top at 716'. Pumped a 50 sk cement plug. Tagged at 670'. Pumped a 280' gel spacer. Pumped a 140 sk surface plug, cement to sur. out of both casings.

Name of Plugging Contractor Klima Well Ser./United Cementing License No.

Address Klima - Claflin, Ks United Cem. - El Dorado, KS

Name of Party Responsible for Plugging Fees: K.C. Resources Inc.

Date of 1-9-99 County of , ss.

Rod Hovland

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein, and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) Rod Hovland

(Address) Oklahoma City, OK



Subscribed and sworn to before me this 17th day of February, 19 99

Sandra Palmer (San Diego, CA)
Notary Public

My Commission Expires: