

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-095-01822-0002

LEASE NAME Alameda Unit O/A TR

WELL NUMBER 5-1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div. C
office within 30 days.

C - NE-NE Ft. from S Section Line

 Ft. from E Section Line

SEC. 27 TWP. 28S RGE. 7W (E) or (W)

COUNTY Kingman

LEASE OPERATOR Texaco Inc.

ADDRESS Box 2420 Tulsa, Oklahoma 74102

PHONE#(018) 560-6000 OPERATORS LICENSE NO. 5153

Date Well Completed 8-26-61

Character of Well Injection

Plugging Commenced 10-14-87

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed ~~10-14-87~~

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Steve VanGieson, Wichita, KS

Is ACO-1 filed? Yes If not, is well log attached?

Producing Formation Lansing-KC Depth to Top 3668 Bottom 4355 T.D. 4476

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	244	none <u>200</u>
				5 1/2	4410	2818 <u>12-15-87</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet, each set.
Perfs. @ 4350-55 squeezed with 150 sks. of cement top of plug @ 4270
Perfs. @ 3674-3668 squeezed with 100 sks. of cement top of plug @ 3440
Shoot pipe loose @ 2818 pull to 244 & pump 75 sks. of cement from 244 to 0

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address Box 506 Liberal, Kansas 67905-0506

STATE OF Kansas COUNTY OF Seward, ss.

D. L. Richter, Asst. Dist. Mgr. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) D. Richter

(Address) P. O. Box 2420, Tulsa, OK 74102

SUBSCRIBED AND SWORN TO before me this 10th day of December, 19 87

Elizabeth A. Legg
Notary Public

My Commission Expires: July 21, 1991