

API NUMBER 15095-01829-0000

LEASE NAME Alameda Unit

WELL NUMBER TR 6-42

1980 Ft. from ^N/₄ Section Line

660 Ft. from E Section Line

SEC. 27 TWP. 28 RGE. 7 (W) or (E)

COUNTY Kingman

Date Well Completed 11-12-61

Plugging Commenced 11-26-90

Plugging Completed 11-29-90

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Texaco Inc.

ADDRESS P.O. Box 779, Kingfisher Okla. 73703

PHONE# (405) 375-5713 OPERATORS LICENSE NO. 5153

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Steve VanGieson (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, Is well log attached? _____

Producing Formation Viola-Simpson Depth to Top 4.358' Bottom 4.363' T.D. 4429'

P.B.T.D. 3625'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Viola-Simpson</u>	<u>Oil</u>	<u>Surface</u>	<u>264'</u>	<u>8 5/8"</u>	<u>264'</u>	<u>0</u>
		<u>0</u>	<u>4424'</u>	<u>5 1/2"</u>	<u>4424'</u>	<u>0</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

11-26-90 GIBP set 3625' with 2 sacks cmt on plug 4 squeeze holes shot 1100' in 5 1/2" Pump 400 sacks cmt plug. Shut in 11-28-90 Shot 4 squeeze holes 600' in 5 1/2" Circulate cmt back up 8 5/8" to surface. Shut well in.
11-29-90 Cut off 3' below surface + weld on plate.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Texaco Inc.

RECEIVED
 License No. 5153
 STATE CORPORATION COMMISSION

Address P.O. Box 326, Enid Okla. 73703

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Texaco Inc.

DEC 6 1990 12-06-90

STATE OF Oklahoma COUNTY OF Kingfisher

CONSERVATION DIVISION
 Wichita, Kansas

Gib Arterburn (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Gib Arterburn

(Address) Box 326 Enid Okla 73701

SUBSCRIBED AND SWORN TO before me this 5 day of December, 19 90

M. J. Jones
 Notary Public

My Commission Expires: September 21, 1991

