

RECEIVED
STATE CORPORATION COMMISSION

APR 11 1975

15-09519/440020


Form CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

CONSERVATION DIVISION
WELL PLUGGING RECORD
Wichita, Kansas

Kingman County, Sec. 27 Twp. 28S Rge. 7 (E) (W)
Location as "NE/CNW&SW4" or footage from lines. C-NW-NW
Lease Owner Texaco Inc.
Lease Name Alameda Unit Tract 6 Well No. 4
Office Address P. O. Box 2420
Character of Well (completed as Oil, Gas or Dry Hole) OIL
Date well completed 5-14-62 19
Application for plugging filed 2-4-75 19
Application for plugging approved 2-19-75 19
Plugging commenced 3-13-75 19
Plugging completed 3-14-75 19
Reason for abandonment of well or producing formation depleted



Locate well correctly on above
Section Plot

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation Depth to top Bottom Total Depth of Well 4435 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	273	none
				4 1/2"	4435	780'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Present PB 1691'. Plugged back 1691-1661' w/4 sx cmt. 1661-490'
w/hvy mud, 490-480' w/rock bridge, 480-3' w/cmt, 3' to surf w/dirt.
Rec 780'

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Co., Inc.
Address Chase, Ks.

STATE OF Oklahoma, COUNTY OF Tulsa, ss.
F. E. ANDERSON (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. E. ANDERSON, Oper. Supt.
P.O. Box 2420, Tulsa, Ok
(Address)

SUBSCRIBED AND SWORN to before me this 8th day of April, 1975

My commission expires 11-25-78

Notary Public

WELL LOG

15-09579/44-00-00

COMPANY TEXACO, INCORPORATED

SEC. 27 T. 28S R. 7W

FARM RICHARDSON

NO. 4

LOC. C-NW, NW


TOTAL DEPTH 4435'

COUNTY KINGMAN CO., KANSAS

COMM. April 26, 1962

COMP. May 8, 1962

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8-5/8" @ 273' w/240 sax.
4 1/2" @ 4434' w/200 sax.

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

85	Surface soil & sand
760	Red bed & shale
1350	Shale & shells w/lime streaks
1715	Lime & shale
2100	Lime
2700	Shale & lime
2785	Lime
2985	Lime & shale
3164	Shale & lime
3245	KXX Shale
3735	Lime
4000	Lime & shale
4064	Chat
4255	Lime
4302	Lime & shale
4335	Shale
4435	Lime
4435	T. D.

RECEIVED
STATE CORPORATION COMMISSION

FEB 6 1975

CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS

County of BARTON

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state the above and foregoing is a true and correct copy of the log of the #4 RICHARDSON well.

Subscribed and sworn to before me this 18th day of May 1962

My Commission Expires: April 14, 1963

NOTARY PUBLIC