


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Kingman County. Sec. 29 Twp. 28 Rge. (E) 7 (W)
Location as "NE/CNW/SW" or footage from lines SE SE NE
Lease Owner Petroleum, Inc.
Lease Name GROOM Well No. 1
Office Address 311 East Third, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 11 19 55
Application for plugging filed August 11 19 55
Application for plugging approved August 11 19 55
Plugging commenced August 11 19 55
Plugging completed August 11 19 55
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4134' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	248'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded up with heavy mud to 210' and placed first plug with 15 sacks cement on top of plug. Mudded up to 25' and set second plug, placed 5 sacks cement on top of plug to base of well cellar.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Garvey Drilling Company
Address R. R. #2 - Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Karl E. Becker (employee of owner) or (owner/contractor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Karl E. Becker
311 East Third, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 11th day of August, 19 55

My commission expires August 8, 1959

Notary Public
STATE CORPORATION COMMISSION
AUG 23 1955
08-26-55
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 29 T 28 R 7W
BOOK PAGE 142 LINE 30

WELL LOG

15-095-00067-0000

COMPANY **Petroleum, Inc.**

SEC. 29 T. 28S R. 7W

FARM **GROOM** NO. **1**


LOC. **SE SE NE**
330' FRL
2310' FRL

TOTAL DEPTH **4134'**

COUNTY **Kingman**

COMM. **July 29, 1955** COMP. **August 11, 1955**

CONTRACTOR **Carvey Drilling Company**



CASING **8-5/8" @ 248' w/175 sax**

ELEVATION **1575' DT**
1577' RB

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

115	Clay & Sand
225	Sand & Red Bed
248	Shale & Shells
345	Shale
1160	Shale & Shells
1360	Anhydrite and Shale
2303	Shale & Lime
2375	Lime
2920	Shale
3080	Lime & Shale
3155	Sand and Shale
3284	Sandy Shale
3425	Lime
3532	Lime & Shale
3941	Lime
4014	Lime & Shale
4084	Mississippi
4102	Lime
4134	Mississippi

Sample Tops

Heebner:	3046 (-1469)
Toronto:	3060 (-1483)
Douglas:	3079 (-1502)
Brown Lime:	3284 (-1707)
Lansing:	3293 (-1716)
Mississippi:	4034 (-2457)

R.T.D. 4134'

State of KANSAS
County of SEDGWICK

PLUGGING
FILE SEC-29 T28 R.7W
BOOK PAGE 142 LINE 30

I, Karl E. Becker of Petroleum, Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the GROOM #1 well

RECEIVED
CORPORATION COMMISSION

AUG 23 1955

Karl E. Becker

Subscribed and sworn to before me this 24th day of August 19 55

My Commission Expires: August 8, 1959

*Alvin M...
NOTARY PUBLIC*