

15-095-20306-000

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

KINGMAN County. Sec. 31 Twp. 28S Rge. 7 (E) 7 (W)

Location as "NE/CNW/SW" or footage from lines NE NW SE
Lease Owner SOUTHERN STATES PETROLEUM CORP.
Lease Name COVINGTON #1-31 Well No. _____
Office Address 641 Denver Club Bldg. Denver, Colorado 80202
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed 6/3 1973
Application for plugging filed 6/3 1973
Application for plugging approved 6/3 1973
Plugging commenced 6/3 1973
Plugging completed 6/3 1973
Reason for abandonment of well or producing formation DRY HOLE



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well RUSSELL BIEBERSTIEN
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4510 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand and redbed		0	292	8 5/8	292	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug 260' w/35 sks
2nd plug 40' w/15 sks
rathole w/2 sks
completed at 8 AM by Allied

RECEIVED
STATE CORPORATION COMMISSION

JUN 6 1973

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor GABBERT-JONES, INC.
Address 830 Sutton Place, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, SS. GABBERT-JONES, INC. (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack W. Gabbert
Jack W. Gabbert, 830 Sutton Place, Wichita, Ks.

5 day of June, 19 73



Nov. 29, 1975

Marjorie Hall
Notary Public.

15-095-203060000

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

NE
4cc
5-470

COVINGTON #1-31
NW SE, Section 31-28S-7W
Kingman County, Kansas

Commenced: May 21, 1973
Completed: June 3, 1973

OPERATOR: SOUTHERN STATES PETROLEUM CORP.

From	Depth To	Formation	Remarks
0	110	Sand	Ran 9 jts of new 24# 8 5/8" csg. set @ 292' cemented w/250 sks common, 2% Gel, 3% CC
110	296	Redbed	
296	1420	Shale	P.D. @ 10:00 PM 5/21/73 2" to 65' cemented w/140 sks common.
1420	1642	Shale-shells	
1642	1960	Shale	Job complete @ 1:30 AM 5/22/1973
1960	3160	Shale & lime	
3160	3370	Shale-sand-lime	
3370	3565	Lime-shale	
3565	3625	Lime	
3625	3715	Lime-shale	
3715	3780	Lime	
3780	4050	Lime-shale	
4050	4341	Lime	
4341	4410	Lime-shale	
4410	4495	Shale	
4495	4510	Simpson	
4510	TD		DRY AND ABANDONED

RECEIVED
STATE CORPORATION COMMISSION
JUN 6 1973
CONSERVATION DIVISION
Wichita, Kansas

I, James S. Sutton, II, certify this is a correct copy of the Drillers' Log for the well drilled in the NW SE, Section 31-28S-7W, Kingman County, Kansas, to the best of my knowledge and belief.

James S. Sutton II
James S. Sutton, II

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 5th day of June, 1973, personally appeared James S. Sutton, II, to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF: I have hereunto set my hand and official seal the day and year last above written.

Marjorie Hall
Marjorie Hall, Notary Public

