

15-095-20130000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Kingman County, Sec. 33 Twp 28S Rge. (E) 7 (W)

Location as "NE/CNW/SE/SW" or footage from lines C SE SE NW

Lease Owner Donald T. Ingling, et al

Lease Name Lecklider Well No. 1

Office Address 615 First National Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 31, 1968

Application for plugging filed Verbal Approval 19

Application for plugging approved Verbal Approval 19

Plugging commenced December 31 1968

Plugging completed December 31 1968

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph J. Warren

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	288'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy rotary mud from 4081 feet (rotary total depth) to 260 feet. Set bottom plug at 260 feet and cemented with 25 sacks of cement. Filled hole with heavy rotary mud to 40 feet. Set plug to 40 feet and cemented with 10 sacks cement, 2 sacks of cement in rathole.

RECEIVED
STATE CORPORATION COMMISSION
JAN 9 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H-30, INC.

Address 200 N. Main St., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Arlo B. Romer (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Arlo B. Romer

200 N. Main, Wichita, Kansas 67202

(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of January, 1969

Martha Hartpence
Martha Hartpence Notary Public.

My commission expires April 21, 1971

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS


15-095-201300000

COMPANY Donald T. Ingling
 FARM Lecklider NO. 1

SEC. 33 T. 28S R. 7W
 LOC. C SE SE NW

TOTAL DEPTH 4081
 COMM. December 19, 1968 COMP. December 31, 1968
 SHOT OR TREATED -
 CONTRACTOR H-30, INC.
 ISSUED

COUNTY Kingman
 KANSAS



CASING
 20 10
 15 8-5/8" 288' cemented w/275 sx cement ELEVATION 1622 KB
 12 6
 13 5
 PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface Soil & Shale	290	<u>SAMPLE TOPS</u>	
Shale	1275		
Shale & Shells	1545	Brown Lime	3324 - 1702
Shale & Lime	1990	Lansing, K.C.	3328 - 1706
Lime	2405	Mississippi Chert	4050 - 2428
Lime & Shale	3505	Rotary T.D.	4081 - 2459
Lime	4081		
Rotary Total Depth	4081		

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Arlo B. Romer

 Arlo B. Romer

STATE OF KANSAS }
 COUNTY OF SEDGWICK } SS:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 8th day of January, 1969.

Martha Hartpence

 Martha Hartpence - Notary Public

My Commission Expires:
 April 21, 1971

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 9 1969
 CONSERVATION DIVISION
 Wichita, Kansas