

15-095-01343-0000


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kingman County, Sec. 34 Twp. 28S Rge. (E) 7 (W)

Location as "NE/CNW/SW" or footage from lines. C NE NE
Lease Owner Pickrell Drilling Company
Lease Name Flickner Well No. 2
Office Address 705 Fourth National Bank Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 25, 1962
Application for plugging filed February 25, 1962
Application for plugging approved February 25, 1962
Plugging commenced February 25, 1962
Plugging completed February 25, 1962
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred W. Hampel
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4388 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	248'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 240'. Set Plug. Cemented with 20 sacks cement. Heavy mud to 40'. Set Plug. Cemented with 10 sacks cement to bottom of cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

MAR 6 1962

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

C. W. Sebitts (employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts
705 Fourth National Bank Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of March, 1962

My commission expires September 24, 1962

Maxine Johnson
Maxine Johnson
Notary Public.



ROTARY DRILLING LOG

15-095-01343-0000

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Bldg.
Wichita 2, Kansas
LOCATION: FLICKNER #2 - G NE NE Sec. 34-28S-7W,
Kingman County, Kansas

Rotary Drilling Commenced 2/12/62
Rotary Drilling Completed 2/25/62

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: 248' (6 jts.) 8 5/8" 20# Surface Casing cemented w/190 sacks cement.
Circulated. No oil string run. D & A

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

		<u>Circulated for Samples</u>
85'	Sand	3675'
249'	Red Rock	3707'
340'	Red Bed & Blue Shale	4030'
1002'	Red Rock & Shale	4035'
1315'	Lime & Shale	4060'
1850'	Lime	4070'
3000'	Lime & Shale	4365'
3161'	Lime, Shale & Sand	4370'
3355'	Lime & Shale	4373'
3805'	Lime	4376'
4020'	Lime & Shale	4379'
4265'	Mississippi	4381'
4385'	Kinderhook	4384'
4388'	Viola R.T.D.	4388'

<u>Slope Test</u>	
1315'	00
2325'	80
3421'	00
4147'	00

<u>S. L. M.</u>	
1500'	
2500'	
3500'	

RECEIVED
STATE CORPORATION COMMISSION
MAR 6 1962
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS.

COUNTY OF SEDGWICK } ss.:

On this 2nd day of March, 19 62, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth:

Given under my hand and seal of office the day and year last above written.

My commission expires: September 24, 1962

Maxine Johnson
Maxine Johnson Notary Public