


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above Section Flat

Kingman County, Sec. 1 Twp. 28S Rge. 8 (E) (W)
Location as "NE/CNW¹/₄SW¹/₄" or footage from lines E/2 NE/4
Lease Owner Beardmore Drilling Company
Lease Name Coleman Well No. 1
Office Address 603 Petroleum Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry Hole
Date well completed October 1 19 51
Application for plugging filed October 1 19 51
Application for plugging approved October 1 19 51
Plugging commenced October 1 19 51
Plugging completed October 1 19 51
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Ruel Durkee, Box 597, McPherson
Producing formation Depth to top Bottom Total Depth of Well 4478 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	252'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from top feet to bottom feet for each plug set.

Mud to 240'; set plug and dump 15 sacks cement;
Mud to 30'; set plug and dump 5 sacks cement
to complete.

RECEIVED
OCT 10 1951 10-10-51

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Beardmore Drilling Company
Address 603 Petroleum Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.


I, Heber Beardmore, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Heber Beardmore*
603 Petroleum Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 5th day of October, 19 51.

Annette A. Kennalby
Notary Public.

My commission expires January 19, 1955



Coleman No. 1

CW $\frac{1}{2}$ NE NE
 Section 1-28S-8W
 Kingman County, Kansas

Drilled for: Beardmore and Champlin
 Drilled by: Beardmore Drilling Company

Casing Record:

8-5/8" 252' w/175 Sacks

Drilling Commenced: September 15, 1951
 Drilling Completed: October 1, 1951

Elevation: 1563' DF
 1561' GR

<u>FORMATION</u>	<u>DEPTH</u>
Sand	30
Red Rock	50
Shale - Shells	1115
Lime - Shale	1240
Lime Broken	1610
Lime - Shale	1810
Shale - Shells	2315
Lime - Shale	2470
Shale - Lime	2855
Lime - Shale	3010
Lime Broken	3245
Lime - Shale	3425
Lime	3555
Lime - Shale	3630
Lime	3835
Shale - Lime	3890
Lime - Shale	3970
Chert	3985
Cherty Lime	4000
Lime	4120
Shale - Shells	4155
Shale - Lime	4225
Shale	4290
Lime - Shale	4330
Lime - Sand	4380
Shale	4455
Lime	4478 T. D.

D & A

DST #1 - 3960-3985
 Rec. 500' heavy gas cut mud; 90' water;
 1/2 million' gas to the surface in 4 minutes;
 flow pressure 180 lbs. Shut in pressure 1250 lbs.
 Drilled 3985-4004; Oil stain in samples.

DST #2 - 3987-4004
 200' gas cut mud; 130' oily salt water; open
 45 min; 1420 BH Shut in pressure 0 open pressure

Tops:

Kansas City 3262
 Mississippi 3958
 Arbuckle 4446

STATE OF KANSAS

OCT 30 1951

STATE OF KANSAS

ss

COUNTY OF SEDGWICK

PLUGGING
 FILE SEC - L.T. & D. & W.
 BOOK PAGE - 114, LINE 10

CONC...

I, the undersigned, being duly sworn on oath state that the above and within statement is a true and correct record and log of the well drilled on the location above-described, to the best of my knowledge and belief.

Beardmore

Subscribed and sworn to before me this 5th day of October, 1951.

Annette A. Kennally
 Notary Public

My Commission Expires:
 January 19, 1955.