


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

15-095-001570000

NORTH



Locate well correctly on above
Section Plat

Kingman County, Sec. 4 Twp. 28 Rge. 8 ~~(E)~~ (W)
Location as "NE/CNW%SW%" or footage from lines NE NE SE
Lease Owner Youngblood & Youngblood
Lease Name McKenna Well No. 1
Office Address Box 552, Oklahoma City, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 3/23/56 19__
Application for plugging filed 3/23/56 19__
Application for plugging approved 3/23/56 19__
Plugging commenced 3/23/56 19__
Plugging completed 3/24/56 19__
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4495 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	232	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGING RECORD

Filled hole with mud to 230 feet, using 1/4 sks hulls and 20 sks cement.
Filled hole with mud to 35 feet, using 1/4 sks hulls and 10 sks cement.
Plugged @ 1:15 a.m. 3/24/56

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Trans Era Petroleum, Inc.
Address 420 W. Douglas Ave., Wichita, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
C. T. Honaker (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. T. Honaker

(Address) _____

SUBSCRIBED AND SWORN TO before me this 27 day of March, 19 56

My commission expires 1-30-57

Margie Cooper
Notary Public.

PLUGGING
FILE SEC 4 T 28 R 8 W
BOOK PAGE 48 LINE 22

MAR 23 1956
03-28-56
CONSERVATION DIVISION
Wichita, Kansas

15095-00157000

Youngblood & Youngblood
McKenna #1

NE NE SE 4-28-8W
Kingman County, Kansas

Trans Era Petroleum, Inc. - Contr.

Elev: 1573 GL
1578 KB

Total Depth: 4495

Comm: 3/7/56
Comp: 3/25/56

Casing:

Cement

8 5/8" @232'

150 sks (2% Gel 1% Cal Chl)

FORMATION	DEPTH
Red Rock	230
Red bed, shale & shells	630
Shale & shells	970
Slat & shale	1120
Lime	1208
Shale & lime, shells	1528
Lime & shale	1717
Lime	1924
Shale & lime	2815
Lime	3037
Lime & shale	3129
Lime, sandy lime & shale	3322
Shale	3324
Brn Lime	3336
Lime	3540
Lime & shale	3592
Limey chert & shale	3621
Lime	3708
Lime, shale chert	3754
Shale & Lime	3765
Shale & Chert	3805
Lime & shale	3931
Shale	3973
Lime	3988
Miss Chert	4045
Shale & Chert	4106
Shale & Lime	4190
Shale, sand, chert	4232
Shale	4309
Viola lime	4361
Shale	4364
Simpson Sand & shale	4398
Sand & shale	4438
Shale & chert	4473
Shale & Lime	4495

Tops: Mississippi 3973
 Kinderhook Shale 4135
 Mississippian 4309
 Simpson Sand 4364

STATE OF KANSAS

COUNTY OF RUSSELL

RECEIVED
 STATE OF KANSAS
 CONSERVATION DIVISION
 ss: Wichita, Kansas

PLUGGING
 FILE SEC 4 T 28 R 8W
 BOOK PAGE 48 LINE 22

I hereby certify that the above information is true and correct to the best of my knowledge.

C. P. Honaker

Subscribed and sworn to before me this 27th day of March, 1956.

Margie Cooper
Notary Public

My commission expires: 1-30-57.